

Section 02922

SODDING

PART 1 GENERAL

1.01 SUMMARY

This Section includes the following:

- A. Restoration of existing lawn areas disturbed by construction shall be by installation of new sod.
- B. Planting of sod within areas designated on Plans for purpose of surface stabilization, channel stabilization or vegetation buffer strips.
- C. Sod is defined as blocks, squares, strips of turf grass, and adhering soil used for vegetative planting. To be placed edge to edge for complete coverage.
- D. Lawn is defined as ground covered with fine textured grass kept neatly mowed.

1.02 MEASUREMENT AND PAYMENT

- A. Unit Prices.
 - 1. Payment for sodding is on square yard basis.
 - 2. Refer to Section 01270 – “Measurement and Payment” for unit price procedures.
- B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment for Work in this Section is included in total Stipulated Price

1.03 REFERENCES

Texas Department of Agriculture – Structural Pest Control Service of the State of Texas.

1.04 SUBMITTALS

Conform to requirements of Section 01330 – “Submittal Procedures”.

1.05 RELATED REQUIREMENTS

- A. Section 01270 – “Measurement and Payment”
- B. Section 01330 – “Submittal Procedures”

- C. Section 01576 – “Waste Material Disposal”

1.06 QUALITY ASSURANCE

- A. Sod only when weather and soil conditions are deemed by Project Manager to be suitable for proper placement.
- B. Water and fertilize new sod.
- C. Guarantee sod to be growing 30 days after substantial completion.
- D. Maintenance Period:
 - 1. Begin maintenance immediately after each section of grass sod is installed and continue for 30 day period from date of substantial completion.
 - 2. Resod unacceptable areas.
 - 3. Water, fertilize, control disease and insect pests, mow, edge, replace unacceptable materials, and perform other procedures consistent with good horticultural practice to ensure normal, vigorous, and healthy growth. Install disease control within guidelines set forth by the Structural Pest Control Service of the State of Texas.
- E. Notify Project Manager 10 days before end of maintenance period for inspection.

1.07 – 1.13 NOT USED

PART 2 PRODUCTS

2.01 MANUFACTURER(S) (NOT USED)

2.02 MATERIAL AND/OR EQUIPMENT

- A. Sod
 - 1. Species: Bermuda (*Cynodon Dactylon*), Buffalo (*Buchloe Dactyloides*), or St. Augustine (*Stenotaphrum Secundatum*) Gulf Coast variety to match existing sod.
 - 2. Contents: 95 percent permanent grass suitable to climate in which it is to be placed; not more than 5 percent weeds and undesirable grasses; good texture, free from obnoxious grasses, roots, stones, and foreign materials.
 - 3. Size: 12 inch wide strips, uniformly 2 inches thick with clean-cut edges.

4. Sod is to be supplied and maintained in healthy condition as evidenced by grass being normal green color.
- B. Fertilizer
Available nutrient percentage by weight: 12 percent nitrogen, 4 percent phosphoric acid, and 8 percent potash; or 15 percent nitrogen, 5 percent phosphoric acid, and 10 percent potash.
- C. Weed and Insect Treatment
Provide acceptable treatment to protect sod from weed and insect infestation. Submit treatment method to Project Manager for approval. Install insect and disease control within guidelines set forth by Structural Pest Control Service of the State of Texas.
- D. Water
Potable, available on-site through Contractor's water trucks. Do not use private resident's water.
- E. Bank Sand
Free of clay lumps, roots, grass, salt, or other foreign material.

2.03 – 2.04 NOT USED

PART 3 EXECUTION

3.01 GENERAL / MANUFACTURER(S) (NOT USED)

3.02 PREPARATION

- A. Verify that soil placement and compaction have been satisfactorily completed. Verify that soil is within allowable range of moisture content.
- B. Top soil shall be free of weeds and foreign material immediately before sodding.
- C. Do not start Work until conditions are satisfactory. Do not start Work during inclement or impending inclement weather.
- D. Rake areas to be sodded smooth, free from unsightly variations, bumps, ridges, or depressions.
- E. Spread 2 inch layer of bank sand over areas to be sodded prior to planting of sod.

- F. Apply fertilizer at rate of 25 pounds per 1000 square feet. Apply after raking soil surface and not more than 48 hours prior to laying sod. Mix thoroughly into upper 2 inches of soil. Lightly water to aid in dissipation of fertilizer

3.03 ERECTION/INSTALLATION/APPLICATION AND/OR CONSTRUCTION

- A. Full Sodding: Lay sod with closely fitted joints leaving no voids and with ends of sod strips staggered. Lay sod within 24 hours of harvesting.
- B. On slopes 2:1 and steeper, lay sod perpendicular to slope and secure every row with wooden pegs at maximum 2 feet on center. Drive pegs flush with soil portion of sod.
- C. Prior to placing sod, on slopes 3:1 or where indicated, place Hold/Gro or Roll Lite or equal over topsoil. Securely anchor in place with posts sunk firmly into ground at maximum 16 feet on center along pitch of slope and equal to width of wire mesh horizontally across slopes.
- D. After sod is laid, irrigate thoroughly to secure 6-inch minimum penetration into soil below sod.
- E. Tamp and roll sod with approved equipment to eliminate minor irregularities and to form close contact with soil bed immediately after planting and watering. Submit type of tamping and rolling equipment to be used to Project Manager for approval, prior to construction.
- F. Maintenance
 - 1. Watering:
 - a. Water lawn areas once a day with minimum ½ inch water for first 3 weeks after area is sodded.
 - b. After 3 week period, water twice a week with ¾ inch of water each time unless comparable amount has been provided by rain.
 - c. Make weekly inspections to determine moisture content of soil unless soil is in frozen condition.
 - d. Water in afternoon or at night to enable soil to absorb maximum amount of water with minimum evaporation.
 - 2. Mowing:
 - a. Mow sod at intervals which shall keep grass height from exceeding 3½ inches.
 - b. Set mower blades at 2½ inches.

- c. Do not remove more than one-half of grass leaf surface.
 - d. Mow sodded areas requiring mowing within 1 month after installation with light-weight rotary type mower. Mow sod only when dry and not in saturated or soft condition. Remove grass clippings during or immediately after mowing.
3. Fertilizer and Pest Control:
- a. Evenly spread fertilizer composite at rate of 40 pounds per 5,000 square feet or as recommended by manufacturer. Do not place fertilizer until 2 weeks after placement of sod.
 - b. Restore bare or thin areas by topdressing with mix of 50 percent sharp sand and 50 percent sphagnum peat moss.
 - c. Apply mixture $\frac{1}{4}$ to $\frac{1}{2}$ inch thick.
 - d. Treat areas of heavy weed and insect infestation as recommended by treatment manufacturer.
4. Restrict all traffic from sodded areas until sod is established or for minimum 10 days during growing season. Use wood lath and plastic tape to cordon sodded areas. Maintain tape and lath throughout for minimum 30 days during growing season.

3.04 – 3.06 NOT USED

3.07 CLEANING

- A. During course of planting, remove excess and waste materials; keep lawn areas clean and take precautions to avoid damage to existing structures, plants, grass, and streets.
- B. Remove barriers, signs, and other Contractor material and equipment from project site at termination of establishment period.
- C. Dispose of unused materials and rubbish in accordance with Section 01576 – “Waste Material Disposal”.

3.08 – 3.10 NOT USED

END OF SECTION