

Section 03315

CONCRETE FOR UTILITY CONSTRUCTION

PART 1 GENERAL

1.01 SUMMARY

This Section includes cast-in-place concrete work for utility construction or rehabilitation, such as slabs on grade, small vaults, site-cast bases for precast units, and in-place liners for manhole rehabilitation.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices.

1. No payment will be made for concrete for utility construction under this Section. Include cost in applicable utility structure.
2. Refer to Section 01270 – “Measurement and Payment” for unit price procedures.

B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment for Work in this Section is included in total Stipulated Price

1.03 REFERENCES

- A. ACI 117 - Specification for Tolerances for Concrete Construction and Materials (ACI 117-10) and Commentary (ACI 117R-10).
- B. ACI 211.1 - Standard Practice for Selecting Proportions for Normal, Heavyweight and Mass Concrete.
- C. ACI 302.1R - Guide for Concrete Floor and Slab Construction.
- D. ACI 304R - Guide for Measuring, Mixing, Transporting, and Placing Concrete.
- E. ACI 308R - Guide to Curing Concrete.
- F. ACI 309R - Guide for Consolidation of Concrete.
- G. ACI 311.5 - Guide for Concrete Plant Inspection and Field Testing of Ready-Mixed Concrete.
- H. ACI 318 - Building Code Requirements for Structural Concrete and Commentary.

- I. ACI 544.3R - Guide for Specifying, Proportioning, and Production of Fiber-Reinforced Concrete.
- J. ASTM A1064/A1064M - Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete.
- K. ASTM A615/A615M REV A - Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement.
- L. ASTM A767/A767M REV B - Standard Specifications for Zinc-Coated (Galvanized) Steel Bars for Concrete Reinforcement.
- M. ASTM A775/A775M REV B - Standard Specification for Epoxy-Coated Steel Reinforcing Bars.
- N. ASTM A820/A820M - Standard Specification for Steel Fibers for Fiber-Reinforced Concrete.
- O. ASTM A884/A884M - Specification for Epoxy-Coated Steel Wire and Welded Wire Reinforcement.
- P. ASTM C31/C31M REV A - Standard Practice for Making and Curing Concrete Test Specimens in the Field.
- Q. ASTM C33/C33M - Standard Specification for Concrete Aggregates.
- R. ASTM C39/C39M REV A - Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens.
- S. ASTM C42/C42M - Standard Test Method for Obtaining and Testing Drilled Cores and Sawed Beams of Concrete.
- T. ASTM C94/C94M REV B - Standard Specification for Ready-Mixed Concrete.
- U. ASTM C138/C138M - Standard Test Method for Density (Unit Weight), Yield, and Air Content (Gravimetric) of Concrete.
- V. ASTM C143/C143M REV A - Standard Test Method for Slump of Hydraulic Cement Concrete.
- W. ASTM C150/C150M - Standard Specification for Portland Cement.
- X. ASTM C172/C172M REV A - Standard Practice for Sampling Freshly Mixed Concrete.
- Y. ASTM C173/C173M - Standard Test Method for Air Content of Freshly Mixed Concrete by Volumetric Method.

- Z. ASTM C231/C231M - Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method.
 - AA. ASTM C260/C260M REV A - Standard Specification for Air-Entraining Admixtures for Concrete.
 - BB. ASTM C309 - Standard Specifications for Liquid Membrane-Forming Compounds for Curing Concrete.
 - CC. ASTM C494/C494M REV A - Standard Specification for Chemical Admixtures for Concrete.
 - DD. ASTM C595/C595M - Standard Specification for Blended Hydraulic Cements.
 - EE. ASTM C685/C685M - Standard Specification for Concrete Made by Volumetric Batching and Continuous Mixing.
 - FF. ASTM C1064/C1064M - Standard Test Method for Temperature of Freshly Mixed Hydraulic-Cement Concrete.
 - GG. ASTM C1077 REV A- Standard Practice for Agencies Testing Concrete and Concrete Aggregate for Use in Construction and Criteria for Testing Agency Evaluation.
 - HH. CRSI MSP-1 - Manual of Standard Practice.
 - II. CRSI - Placing Reinforcing Bars.
 - JJ. CPMB 100-07 – Part 2 – Plant Control Systems
 - KK. Corps of Engineers CRD-C572 – Specifications for Polyvinylchloride Waterstop.
- 1.04 SUBMITTALS
- A. Conform to requirements of Section 01330 – “Submittal Procedures”.
 - B. Submit proposed mix design and test data for each type and strength of concrete in Work.
 - C. Submit laboratory reports prepared by independent testing laboratory stating that materials used comply with requirements of this Section.
 - D. Submit manufacturer’s mill certificates for reinforcing steel. Provide specimens for testing when required by Project Manager.
 - E. Submit certification from concrete supplier that materials and equipment used to produce and deliver concrete comply with this Specification.

- F. When required on Plans, submit shop drawings showing reinforcement type, quantity, size, length, location, spacing, bending, splicing, support, fabrication details, and other pertinent information.
- G. For waterstops, submit product information sufficient to indicate compliance with this Section, including manufacturer's descriptive literature and specifications

1.05 RELATED REQUIREMENTS

- A. Section 01270 – “Measurement and Payment”
- B. Section 01330 – “Submittal Procedures”
- C. Section 01454 – “Testing Laboratory Services”

1.06 – 1.07 NOT USED

1.08 DELIVERY, STORAGE, AND HANDLING

- A. Cement: Store cement off of ground in well-ventilated, weatherproof building.
- B. Aggregate: Prevent mixture of foreign materials with aggregate and preserve gradation of aggregate.
- C. Reinforcing Steel: Store reinforcing steel to protect it from mechanical injury and formation of rust. Protect epoxy-coated steel from damage to coating.

1.09 – 1.13 NOT USED

PART 2 PRODUCTS

2.01 MANUFACTURER(S)

- A. PVC Waterstops: Flat Strip and Center-Bulb Waterstops:
 - 1. Kirkhill Rubber Co., Brea, California
 - 2. Water Seals, Inc., Chicago, Illinois
 - 3. Progress Unlimited, Inc., New York, New York
 - 4. Greenstreak Plastic Products Co., St. Louis, Missouri
 - 5. Approved equal.
- B. Resilient Waterstops, Adhesive:
 - 1. Synko-Flex Preformed Plastic Adhesive Waterstop, Synko-Flex Products, Inc.

2. Approved equal.

2.02 MATERIALS AND/OR EQUIPMENT

A. Concrete Materials

1. Cementitious Material:
 - a. Portland Cement: ASTM C150/C150M, Type II, unless use of Type III is authorized by Project Manager; or ASTM C595/C595M, Type IP. For concrete in contact with sewage use Type II cement.
 - b. When aggregates are potentially reactive with alkalis in cement, use cement not exceeding 0.6 percent alkali content in form of $\text{Na}_2\text{O} + 0.658\text{K}_2\text{O}$.
2. Water: Clean, free from harmful amounts of oils, acids, alkalis, or other deleterious substances, and meeting requirements of ASTM C94/C94M REV B.
3. Aggregate:
 - a. Coarse Aggregate: ASTM C33/C33M. Unless otherwise indicated, use following ASTM standard sizes: No. 357 or No. 467; No. 57 or No. 67, No. 7. Maximum size: Not larger than 1/5 of narrowest dimension between sides of forms, nor larger than 3/4 of minimum clear spacing between reinforcing bars.
 - b. Fine Aggregate: ASTM C33/C33M.
 - c. Determine potential reactivity of fine and coarse aggregate in accordance with Appendix to ASTM C33/C33M.
4. Air Entraining Admixtures: ASTM C260/C260M REV A.
5. Chemical Admixtures:
 - a. Water Reducers: ASTM C494/C494M REV A, Type A.
 - b. Water Reducing Retarders: ASTM494/C494M REV A, Type D.
 - c. High Range Water Reducers (Superplasticizers): ASTM C 494/C494M REV A, Types F and G.
6. Prohibited Admixtures: Admixtures containing calcium chloride, thiocyanate, or materials that contribute free chloride ions in excess of 0.1 percent by weight of cement.

7. Reinforcing Steel:
 - a. Use new billet steel bars conforming to ASTM A615/A615M REV A, ASTM A767/A767M REV B, or ASTM A775/A775M REV B, grade 40 or grade 60, as shown on Plans. Use deformed bars except where smooth bars are specified. When placed in Work, keep steel free of dirt, scale, loose or flaky rust, paint, oil or other harmful materials.
 - b. Where shown, use welded wire fabric with wire conforming to ASTM A1064/A1064M or ASTM A884/A884M. Supply gauge and spacing shown, with longitudinal and transverse wires electrically welded together at points of intersection with welds strong enough not to be broken during handling or placing.
 - c. Wire: ASTM A1064/A1064M. Use 16½ gauge minimum for tie wire, unless otherwise indicated.
8. Fiber:
 - a. Fibrillated Polypropylene Fiber:
 - 1) Addition Rate: 1.5 pounds of fiber per cubic yard of concrete.
 - 2) Physical Properties:
 - a) Material: Polypropylene
 - b) Length: ½-inch or graded
 - c) Specific Gravity: 0.91
 - 3) Acceptable Manufacturer: W. R. Grace Company, Fibermesh, or approved equal.
 - b. Steel Fiber: Comply with applicable provisions of ACI 544.3R and ASTM A820/A820M.
 - 1) Ratio: 50 to 200 pounds of fiber per cubic yard of concrete.
 - 2) Physical Properties
 - a) Material: Steel
 - b) Aspect Ratio (for fiber lengths of 0.5 to 2.5 inch, length divided by diameter or equivalent diameter): 30:1 to 100:1

- c) Specific Gravity: 7.8
 - d) Tensile Strength: 40-400 ksi.
 - e) Young's Modulus: 29,000 ksi
 - f) Minimum Average Tensile Strength: 50,000 psi
 - g) Bending Requirements: Withstand bending around 0.125-inch diameter mandrel to angle of 90 degrees, at temperatures not less than 60 degrees F, without breaking
9. Curing Compounds: Type 2 white-pigmented liquid membrane-forming compounds conforming to ASTM C309.

B. Form Work Materials

1. Lumber and Plywood: Seasoned and of good quality, free from loose or unsound knots, knot holes, twists, shakes, decay and other imperfections which would affect strength or impair finished surface of concrete. Use S4S lumber for facing or sheathing. Forms for bottoms of caps: At least 2 inch (nominal) lumber, or $\frac{3}{4}$ inch form plywood backed adequately to prevent misalignment. For general use, provide lumber of 1-inch nominal thickness or form plywood of approved thickness.
2. Form work for Exposed Concrete Indicated to Receive Rubbed Finish: Form or form-lining surfaces free of irregularities; plywood of $\frac{1}{4}$ inch minimum thickness, preferably oiled at mill.
3. Chamfer Strips and Similar Moldings: Redwood, cypress, or pine that will not split when nailed and which can be maintained to true line. Use mill-cut molding dressed on all faces.
4. Form Ties: Metal or fiberglass of approved type with tie holes not larger than $\frac{7}{8}$ inch in diameter. Do not use wire ties or snap ties.
5. Metal Forms: Clean and in good condition, free from dents and rust, grease, or other foreign materials that tend to disfigure or discolor concrete in gauge and condition capable of supporting concrete and construction loads without significant distortion. Countersink bolt and rivet heads on facing sides. Use only metal forms which present smooth surface and which line up properly.

C. Measurement of Materials

1. Measure dry materials by weight, except volumetric proportioning may be used when concrete is batched and mixed in accordance with ASTM C685/C685M.

2. Measure water and liquid admixtures by volume.

D. Design Mix

1. Use design mixes prepared by certified testing laboratory in accordance with ASTM C1077 REV A and conforming to requirements of this section.
2. Proportion concrete materials based on ACI 211.1 to comply with durability and strength requirements of ACI 318, Chapters 4 and 5, and this specification. Prepare mix design of Class A concrete so minimum cementitious content is 564 pounds per cubic yard. Submit concrete mix designs to Project Manager for review.
3. Proportioning on basis of field experience or trial mixtures in accordance with requirements at Section 5.3 of ACI 318 may be used, when approved by Project Manager.
4. Classification:

CLASS	TYPE	MINIMUM COMPRESSIVE STRENGTH (LBS/SQ. IN.)		MAXIMUM W/C RATIO	AIR CONTENT (PERCENT)	CONSISTENCY RANGE IN SLUMP (INCHES)
		7-DAY	28-DAY			
		A	Structural			
B	Pipe Block Fill, Thrust Block	----	1,500	----	4± 1	5 to 7

*When ASTM C494/C494M REV A, Type F or Type G admixture is used to increase workability, this range may be 6 to 9.

5. Add steel or polypropylene fibers only when called for on Plans or in another section of these Specifications.
6. Determine air content in accordance with ASTM C138/C138M, ASTM C173/C173M or ASTM C231/C231M.
7. Use of Concrete Classes: Use classes of concrete as indicated on Plans and other Specifications. Use Class B for unreinforced concrete used for plugging pipes, seal slabs, thrust blocks, trench dams, tunnel inverts and concrete fill unless indicated otherwise. Use Class A for all other applications.

E. Waterstops

1. PVC Waterstops
 - a. Extrude from virgin polyvinyl chloride elastomer. Use no reclaimed or scrap material. Submit waterstop manufacturer's current test reports and manufacturer's written certification that material furnished meets or exceeds Corps of Engineers Specification CRD-C572 and other specified requirements.
 - b. Flat Strip and Center-Bulb Waterstops:

Thickness: not less than 3/8 inch
2. Resilient Waterstop: where shown on Plans; either bentonite- or adhesive-type material.
 - a. Bentonite Waterstop:
 - 1) Material: 75 percent bentonite, mixed with butyl rubber-hydrocarbon containing less than 1.0 percent volatile matter, and free of asbestos fibers or asphaltics.
 - 2) Manufacturer's rated temperature ranges: For application, 5 to 125 degrees F; in service, -40 to 212 degrees F.
 - 3) Cross-sectional dimensions, unexpanded waterstop: 1 inch by 3/4 inch
 - 4) Provide with adhesive backing capable of producing excellent adhesion to concrete surfaces.
 - b. Adhesive Waterstop:
 - 1) Preformed plastic adhesive waterstop at least 2 inches in diameter.
 - 2) Supplied wrapped completely by 2 part protective paper.
 - 3) Submit independent laboratory tests verifying that material seals joints in concrete against leakage when subjected to minimum of 30 psi water pressure for at least 72 hours.
 - 4) Provide primer, to be used on hardened concrete surfaces, from same manufacturer who supplies waterstop material.

2.03 FABRICATION

A. Production Methods

Use either ready-mixed concrete conforming to requirements of ASTM C94/C94M REV B, or concrete produced by volumetric batching and continuous mixing in accordance with ASTM C685/C685M.

2.04 SOURCE QUALITY CONTROL (NOT USED)

PART 3 EXECUTION

3.01 – 3.02 NOT USED

3.03 ERECTION/INSTALLATION APPLICATION AND/OR CONSTRUCTION

A. Forms and Shoring

1. Provide mortar-tight forms sufficient in strength to prevent bulging between supports. Set and maintain forms to lines designated such that finished dimensions of structures are within tolerances specified in ACI 117. Construct forms to permit removal without damage to concrete. Forms may be given slight draft to permit ease of removal. Provide adequate clean out openings. Before placing concrete, remove extraneous matter from within forms.
2. Install rigid shoring having no excessive settlement or deformation. Use sound timber in shoring centering. Shim to adjust and tighten shoring with hardwood timber wedges.
3. Design Loads for Horizontal Surfaces of Forms and Shoring: Minimum fluid pressure, 175 pounds per cubic foot; live load, 50 pounds per square foot. Maximum unit stresses: 125 percent of allowable stresses used for form materials and for design of support structures.
4. Back form work with sufficient number of studs and wales to prevent deflection.
5. Re-oil or lacquer liner on job before using. Facing may be constructed of $\frac{3}{4}$ inch plywood made with waterproof adhesive backed by adequate studs and wales. In such cases, form lining will not be required.
6. Unless otherwise indicated, form outside corners and edges with triangular $\frac{3}{4}$ inch chamfer strips (measured on sides).
7. Remove metal form ties to depth of at least $\frac{3}{4}$ inch from surface of concrete. Do not burn off ties. Do not use pipe spreaders. Remove spreaders which are separate from forms as concrete is being placed.
8. Treat facing of forms with approved form coating before concrete is placed. When directed by Project Manager, treat both sides of face forms with coating.

Apply coating before reinforcement is placed. Immediately before concrete is placed, wet surface of forms which will come in contact with concrete.

B. Placing Reinforcement

1. Place reinforcing steel accurately in accordance with approved Plans. Secure steel adequately in position in forms to prevent misalignment. Maintain reinforcing steel in place using approved concrete and hot-dip galvanized metal chairs and spacers. Place reinforcing steel in accordance with CRSI Publication "Placing Reinforcing Bars." Request inspection of reinforcing steel by Project Manager and obtain acceptance before concrete is placed.
2. Minimum spacing center-to-center of parallel bars: $2\frac{1}{2}$ times nominal bar diameter. Minimum cover measured from surface of concrete to face of reinforcing bar unless shown otherwise on Plans: 3 inches for surfaces cast against soil or subgrade, 2 inches for other surfaces.
3. Detail bars in accordance with ACI 318. Fabricate reinforcing steel in accordance with CRSI Publication MSP-1, "Manual of Standard Practice." Bend reinforcing steel to required shape while steel is cold. Excessive irregularities in bending will be cause for rejection.
4. Do not splice bars without written approval of Project Manager. Approved bar bending schedules or placing drawings constitute written approval. Splice and development length of bars shall conform to ACI 318, Chapters 7 and 12, and as shown on Plans. Stagger splices or locate at points of low tensile stress.

C. Embedded Items

1. Install conduit and piping as shown on Plans. Accurately locate and securely fasten conduit, piping, and other embedded items in forms.
2. Install waterstops according to manufacturer's instructions. Securely position waterstops at joints as indicated on Plans. Protect waterstops from damage or displacement during concrete placing operations.

D. Batching, Mixing and Delivery of Concrete

1. Measure, batch, mix, and deliver ready-mixed concrete in accordance with ASTM C94, Sections 8 through 11. Produce ready-mixed concrete using automatic batching system as described in CPMB 100-07, Part 2 - Plant Control Systems.
2. Measure, mix and deliver concrete produced by volumetric batching and continuous mixing in accordance with ASTM C685/C685M, Sections 6 through 8.

3. Maintain concrete workability without segregation of material and excessive bleeding. Obtain approval of Project Manager before adjustment and change of mix proportions.
4. Ready-mixed concrete delivered to site shall be accompanied by batch tickets providing information required by ASTM C94, Section 16. Concrete produced by continuous mixing shall be accompanied by batch tickets providing information required by ASTM C685/C685M, Section 14.
5. When adverse weather conditions affect quality of concrete, postpone concrete placement. Do not mix concrete when air temperature is at or below 40 degrees F and falling. Concrete may be mixed when temperature is 35 degrees F and rising. Take temperature readings in shade, away from artificial heat. Protect concrete from temperatures below 32 degrees F until concrete has cured for minimum of 3 days at 70 degrees F or 5 days at 50 degrees F.
6. Clean, maintain and operate equipment so that it thoroughly mixes material as required.
7. Hand-mix only when approved by Project Manager.

E. Placing Concrete

1. Give sufficient advance notice to Project Manager (at least 24 hours prior to commencement of operations) to permit inspection of forms, reinforcing steel, embedded items and other preparations for placing concrete. Place no concrete prior to Project Manager's approval.
2. Schedule concrete placing to permit completion of finishing operations in daylight hours. However, when necessary to continue after daylight hours, light site as required. When rainfall occurs after placing operations are started, provide covering to protect Work.
3. Use troughs, pipes and chutes lined with approved metal or synthetic material in placing concrete so that concrete ingredients are not separated. Keep chutes, troughs and pipes clean and free from coatings of hardened concrete. Allow no aluminum material to be in contact with concrete.
4. Limit free fall of concrete to 4 feet. Do not deposit large quantities of concrete at one location so that running or working concrete along forms is required. Do not jar forms after concrete has taken initial set; do not place strain on projecting reinforcement or anchor bolts.
5. Use tremies for placing concrete in walls and similar narrow or restricted locations. Use tremies made in sections, or provide in several lengths, so that outlet may be adjusted to proper height during placing operations.

6. Place concrete in continuous horizontal layers approximately 12 inches thick. Place each layer while layer below is still plastic.
7. Compact each layer of concrete with concrete spading implements and mechanical vibrators of approved type and adequate number for size of placement. When immersion vibrators cannot be used, use form vibrators. Apply vibrators to concrete immediately after depositing. Move vibrator vertically through layer of concrete just placed and several inches into plastic layer below. Do not penetrate or disturb layers previously placed which have partially set. Do not use vibrators to aid lateral flow concrete. Closely supervise consolidation to ensure uniform insertion and duration of immersion.
8. Handling and Placing Concrete: Conform to ACI 302.1R, ACI 304R and ACI 309R.

F. Waterstops

1. Embed waterstops in concrete across joints as shown. Waterstops shall be continuous for extent of joint; make splices necessary to provide continuity in accordance with manufacturer's instructions. Support and protect waterstops during construction operations; repair or replace waterstops damaged during construction.
2. Install waterstops in concrete on one side of joints, leaving other side exposed until next pour. When waterstop will remain exposed for 2 days or more, shade and protect exposed waterstop from direct rays of sun during entire exposure and until exposed portion of waterstop is embedded in concrete.
3. Splicing PVC Waterstops:
 - a. Splice waterstops by heat-sealing adjacent waterstop sections in accordance with manufacturer's printed instructions.
 - b. Butt end-to-end joints of two identical waterstop sections may be made in forms during placement of waterstop material.
 - c. Prior to placement in form work, prefabricate waterstop joints involving more than two ends to be joined together, angle cut, alignment change, or joining of two dissimilar waterstop sections, allowing not less than 24 inch long strips of waterstop material beyond joint. Upon inspection and approval by Project Manager, install prefabricated waterstop joint assemblies in form work, and butt-weld ends of 24-inch strips to straight-run portions of waterstop in forms.
4. Setting PVC Waterstops:

- a. Correctly position waterstops during installation. Support and anchor waterstops during progress of Work to ensure proper embedment in concrete and to prevent folding over of waterstop by concrete placement. Locate symmetrical halves of waterstops equally between concrete pours at joints, with center axis coincident with joint openings. Thoroughly work concrete in joint vicinity for maximum density and imperviousness.
 - b. Where waterstop in a vertical wall joint does not connect with any other waterstop, and is not intended to be connected to waterstop in future concrete placement, terminate waterstop 6 inches below top of wall.
5. Replacement of Defective Field Joints: Replace waterstop field joints showing evidence of misalignment, offset, porosity, cracks, bubbles, inadequate bond or other defects with products and joints complying with Specifications.
6. Resilient Waterstop:
- a. Install resilient waterstop in accordance with manufacturer's instructions and recommendations.
 - b. When requested by Project Manager, provide technical assistance by manufacturer's representative in field at no additional cost.
 - c. Use resilient waterstop only where complete confinement by concrete is provided; do not use in expansion or contraction joints.
 - d. Where resilient waterstop is used in combination with PVC waterstop, lap resilient waterstop over PVC waterstop minimum of 6 inches and place in contact with PVC waterstop. Where crossing PVC at right angles, melt PVC ribs to form smooth joining surface.
 - e. At free top of walls without connecting slabs, stop resilient waterstop and grooves (where used) 6 inches from top in vertical wall joints.
 - f. Bentonite Waterstop:
 - 1) Locate bentonite waterstop as near as possible to center of joint and extend continuous around entire joint. Minimum distance from edge of waterstop to face of member: 5 inches.
 - 2) Where thickness of concrete member to be placed on bentonite waterstop is less than 12 inches, place waterstop in grooves at least $\frac{3}{4}$ inch deep and $1\frac{1}{4}$ inches wide formed or ground into concrete. Minimum distance from edge of waterstop placed in groove to face of member: 2.5 inches.

- 3) Do not place bentonite waterstop when waterstop material temperature is below 40 degrees F. Waterstop material may be warmed so that it remains above 40 degrees F during placement but means used to warm it shall in no way harm material or its properties. Do not install waterstop where air temperature falls outside manufacturer's recommended range.
 - 4) Place bentonite waterstop only on smooth and uniform surfaces; grind concrete smooth when necessary to produce satisfactory substrate, or bond waterstop to irregular surfaces using epoxy grout which completely fills voids and irregularities beneath waterstop material. Prior to installation, wire brush concrete surface to remove laitance and other substances that may interfere with bonding of epoxy.
 - 5) In addition to adhesive backing provided with waterstop, secure bentonite waterstop in place with concrete nails and washers at 12 inch maximum spacing.
- g. Adhesive Waterstop:
- 1) With wire brush thoroughly clean concrete surface on which waterstop is to be placed and then coat with primer.
 - 2) If surface is too rough to allow waterstop to form complete contact, grind to form adequately smooth surface.
 - 3) Install waterstop with top protective paper left in place. Overlap joints between strips minimum of 1 inch and cover back over with protective paper.
 - 4) Do not remove protective paper until just before final form work completion. Place concrete immediately. Time that waterstop material is uncovered prior to concrete placement shall be minimized and shall not exceed 24 hours.

G. Construction Joints

1. Definitions:

- a. Construction joint: Contact surface between plastic (fresh) concrete and concrete that has attained initial set.
- b. Monolithic: Manner of concrete placement to reduce or eliminate construction joints; joints other than those indicated on Plans will not be permitted without written approval of Project Manager. Where so

approved, make additional construction joints with details equivalent to those indicated for joints in similar locations.

- c. Preparation for Construction Joints: Roughen surface of concrete previously placed, leaving some aggregate particles exposed. Remove laitance and loose materials by sandblasting or high-pressure water blasting. Keep surface wet for several hours prior to placing of plastic concrete.

H. Curing

1. Comply with ACI 308R. Cure by preventing loss of moisture, rapid temperature change and mechanical injury for period of 7 curing days when Type II or IP cement has been used and for 3 curing days when Type III cement has been used. Start curing as soon as free water has disappeared from concrete surface after placing and finishing. A curing day is any calendar day in which temperature is above 50 degrees F for at least 19 hours. Colder days may be counted when air temperature adjacent to concrete is maintained above 50 degrees F. In continued cold weather, when artificial heat is not provided, removal of forms and shoring may be permitted at end of calendar days equal to twice required number of curing days. However, leave soffit forms and shores in place until concrete has reached specified 28 day strength, unless directed otherwise by Project Manager.
2. Cure formed surfaces not requiring rubbed-finished surface by leaving forms in place for full curing period. Keep wood forms wet during curing period. Add water as needed for other types of forms. Or, at Contractor's option, forms may be removed after 2 days and curing compound applied.
3. Rubbed Finish:
 - a. At formed surfaces requiring rubbed finish, remove forms as soon as practicable without damaging surface.
 - b. After rubbed-finish operations are complete, continue curing formed surfaces by using either approved curing/sealing compounds or moist cotton mats until normal curing period is complete.
4. Unformed Surfaces: Cure by membrane curing compound method.
 - a. After concrete has received final finish and surplus water sheen has disappeared, immediately seal surface with uniform coating of approved curing compound, applied at rate of coverage recommended by manufacturer or as directed by Project Manager. Do not apply less than 1 gallon per 180 square feet of area. Provide satisfactory means to properly control and check rate of application of compound.

- b. Thoroughly agitate compound during use and apply by means of approved mechanical power pressure sprayers equipped with atomizing nozzles. For application on small miscellaneous items, hand-powered spray equipment may be used. Prevent loss of compound between nozzle and concrete surface during spraying operations.
- c. Do not apply compound to dry surface. When concrete surface has become dry, thoroughly moisten surface immediately prior to application. At locations where coating shows discontinuities, pinholes or other defects, or when rain falls on newly coated surface before film has dried sufficiently to resist damage, apply additional coat of compound at specified rate of coverage.

I. Removal of Forms and Shoring

- 1. Remove forms from surfaces requiring rubbing only as rapidly as rubbing operation progresses. Remove forms from vertical surfaces not requiring rubbed-finish when concrete has aged for required number of curing days. When curing compound is used, do not remove forms before 2 days after concrete placement.
- 2. Leave soffit forms and shores in place until concrete has reached specified 28-day strength, unless directed otherwise by Project Manager.

J. Finishing

- 1. Patch honeycomb, minor defects and form tie holes in concrete surfaces with cement mortar mixed one part cement to two parts fine aggregate. Repair defects by cutting out unsatisfactory material and replacing with new concrete, securely keyed and bonded to existing concrete. Finish to make junctures between patches and existing concrete as inconspicuous as possible. Use stiff mixture and thoroughly tamp into place. After each patch has stiffened sufficiently to allow for greatest portion of shrinkage, strike off mortar flush with surface.
- 2. Apply rubbed finish to exposed surfaces of formed concrete structures as noted on Plans. After pointing has set sufficiently, wet surface with brush and perform first surface rubbing with No. 16 carborundum stone, or approved equal. Rub sufficiently to bring surface to paste, to remove form marks and projections, and to produce smooth, dense surface. Add cement to form surface paste as necessary. Spread or brush material, which has been ground to paste, uniformly over surface and allow to reset. In preparation for final acceptance, clean surfaces and perform final finish rubbing with No. 30 carborundum stone or approved equal. After rubbing, allow paste on surface to reset; then wash surface with clean water. Leave structure with clean, neat and uniform-appearing finish.

3. Apply wood float finish to concrete slabs.

3.04 REPAIR/RESTORATION

A. Defective Work

Immediately repair defective Work discovered after forms have been removed. When concrete surface is bulged, uneven, or shows excess honeycombing or form marks which cannot be repaired satisfactorily through patching, remove and replace entire section.

3.05 FIELD QUALITY CONTROL

- #### A. Testing shall be performed under provisions of Section 01454 – “Testing Laboratory Services”.

- #### B. Unless otherwise directed by Project Manager, following minimum testing of concrete is required. Testing shall be performed by qualified individuals employed by approved independent testing agency, and conform to requirements of ASTM C1077 REV A.

1. Take concrete samples in accordance with ASTM C172/C172M REV A.

2. Make one set of four compression test specimens for each mix design at least once per day and for each 150 cubic yards or fraction thereof. Make cure and test specimens in accordance with ASTM C31/C31M REV A and ASTM C39/C39M REV A.

3. When taking compression test specimens, test each sample for slump according to ASTM C143/C143M REV A, for temperature according to ASTM C1064/C1064M, for air content according to ASTM C231/C231M, and for unit weight according to ASTM C138/C138M.

4. Inspect, sample and test concrete in accordance with ASTM C94, Section 13, 14, and 15, and ACI 311.5-5R.

- #### C. Test Cores: Conform to ASTM C42/C42M.

- #### D. Testing High Early Strength Concrete: When Type III cement is used in concrete, specified 7 day and 28 day compressive strengths shall be applicable at 3 and 7 days, respectively.

- #### E. If 7-day or 3-day test strengths (as applicable for type of cement being used) fail to meet established strength requirements, extended curing or resumed curing on those portions of structure represented by test specimens may be required. When additional curing fails to produce required strength, strengthening or replacement of portions of

structure which fail to develop required strength may be required by Project Manager, at no additional cost.

3.06 – 3.08 NOT USED

3.09 PROTECTION

- A. Protect concrete against damage until final acceptance by the Owner.
- B. Protect fresh concrete from damage due to rain, hail, sleet, or snow. Provide protection while concrete is still plastic, and whenever precipitation is imminent or occurring.
- C. Do not backfill around concrete structures or subject them to design loadings until components of structure needed to resist loading are complete and have reached specified 28 day compressive strength, except as authorized otherwise by Project Manager.

3.10 SCHEDULES (NOT USED)

END OF SECTION